



SECTION J-J

Galvanized steel caterpillar safety hasp with 2 or 3 links. Minimum overall length of slotted and hinged flaps = 7 3/4". 2 link hasp shown.



DETAIL A

2" x 3"± galvanized shim plate. Thickness as required for sex bolt fit up.



DETAIL B

## NOTES:

1. Masonry anchors to be installed after the grout in the block cells has attained specified strength.
2. Contractor may submit alternative gate locking assemblies for approval by the Engineer.
3. See other sheets for gate details.

- ① 4 - sex bolts with 1/4" - 20 flat head corrosion resistant machine screws.
- ② 4 - 1/4" Ø x 3" long flat head sleeve type corrosion resistant masonry anchors.
- ③ Galvanized shim plate. Size as required to match hasp staple plate. Thickness as required for sex bolt fit up.

STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION

# **SOUND WALL MASONRY BLOCK ACCESS GATE LOCKING DETAILS**

NO SCALE

**B15-14**

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
<p><i>Douglas J. Dunne</i> REGISTERED CIVIL ENGINEER</p> <p>May 1, 2006 PLANS APPROVAL DATE</p> <p><i>Douglas J. Dunne</i> No. C47240 Exp. 12-31-07 CIVIL STATE OF CALIFORNIA</p> <p><small>The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.</small></p> <p>To get to the Caltrans web site go to <a href="http://www.dot.ca.gov">http://www.dot.ca.gov</a></p>					